## BANGALORE DIVISION.

*Notification dated 8th November 1906.*

The attention of the public is invited to the Notification in the *Mysore Gazette*, No. 44, dated 8th November 1906, calling for tenders for construction of a new Matt at Sivaganga in the Nelamangala Taluk.

*N. B.*—Item No. 22, Rolled Steel Girders and Joists.

As published in the Notification dated 8th November 1906 under column "Per" "Cwt" should be substituted for "C.ft."

B. S. VENKATACHARIAR,
*Executive Engineer.*

## KADUR DIVISION.

*Dated 8th November 1906.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 1st December 1906, for constructing Public Works Department officials quarters at Balgadi, Koppa Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500, in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Public Works Department officials quarters at Balgadi, Koppa Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Western Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing Public Works Department Officials Quarters at Balgadi, Koppa Taluk.

| No. | Items of work | Per | Quantity. |
|---|---|---|---|
| | *For one Block.* | | |
| 1 | Earthwork, excavation and filling in basement ... ... ... | C. yd. | 139 |
| 2 | Burnt stone in chunam, filling foundation and basement ... | C. ft. | 3,009 |
| 3 | Burnt brick in chunam, superstructure ... ... | ,, | 3,823 |
| 4 | Flat archwork, brick in chunam ... ... ... | ,, | 127 |
| 5 | Burnt stone slabs roughly dressed 4" thick ... ... | S. ft. | 306 |
| 6 | Cement concrete pillars ... ... ... ... | C. ft. | 26 |
| 7 | Pointing with cement to basement ... ... ... | Sqr. | 1·78 |
| 8 | Plastering with chunam two coats .. ... ... | ,, | 73·80 |
| 9 | White and color washings ... ... ... | ,, | 75·58 |
| 10 | Cornice, brick in chunam, 9" deep ... ... ... | R. ft. | 56 |
| 11 | Flooring with concrete 4" thick and smoothening ... | Sqr. | 10·35 |
| 12 | Flooring with Mangalore tiles over 3" concrete bed and cement pointing ... ... ... ... | ,, | 2·53 |
| 13 | Roofing with 1st class Mangalore tiles excluding reepers ... | ,, | 26·36 |
| 14 | Providing sheet iron chimneys No. 4 ... ... | Lump sum rupees | |
| 15 | Cisterns and pipes to bath and kitchen ... ... | Do | |